

Site Access Over Ruxton Creek

SUPPORTING THE RESIDENTS OF MAINTOU SPRINGS, COLORADO

Matrax Inc. worked with City of Manitou Spring officials to re-establish a residential access road for community residents using a 55' long modular bridge.

Flooding from excessive rainfall over the past few years had resulted in degradation of an earthen culvert system spanning Ruxton Creek and was deemed unsafe for vehicular traffic by local officials.

The HS25 capacity modular steel bridge was fabricated in 4 weeks, shipped to the site on a flatbed truck, lifted in place by a small crane, and ready to serve local traffic in a matter of hours.

